

Horizontal sidewall sprinklers

Project information

Job name:	Location:
Engineer:	Date submitted:
Contractor:	Submitted by:
Manufacturer's representative:	Approved by:

Technical data

Temp/pressure ratings	73 °F (23 °C) at 160 psi (11 bar)
	180 °F (82 °C) at 100 psi (6.9 bar)
	200 °F (93 °C) at 80 psi (5.5 bar)
Prop 65 label required?	Yes



Part name	Part no.	Weight per UOM [lbs/UOM]
LF Recessed Horizontal Sidewall Sprinkler, 155F, 4.2 K-factor, White	LF74300HW	0.15
LF Recessed Horizontal Sidewall Sprinkler, 175F, 4.2 K-factor, White	LF74301HW	0.15
LF Flat Concealed Horizontal Sidewall Sprinkler, 165F, 4.0 K-factor	LF74000HS	0.15

Installation

-

Related applications

AquaSAFE™ Fire Safety Systems

Footnotes

-

Contact information

Uponor Inc.
5925 148th Street West
Apple Valley, MN 55124
T 800.321.4739
F 952.891.2008

Uponor Ltd.
6510 Kennedy Road
Mississauga, ON L5T 2X4
T 888.594.7726
F 800.638.9517